STAMP OF APPROVAL	
LAYOUT	01/50
LAYOUT SANCTIONED NO. B.P./EC/WAKAD/08/2023 DATED : 09/06/2023	
LAYOUT SANCTIONED VIDE NO.BP/WAKAD/LAYOUT/89/2023 DATED : 23.06.2023	
SANCTIONED NO. B.P./WAKAD/143/2023 DATED : 13/09/2023	
SANCTIONED NO. B.P./WAKAD/179/2023 DATED : 09/11/2023	
SANCTIONED NO. B.P./WAKAD/85/2024 DATED : 24/06/2024	
SANCTIONED NO. B.P./WAKAD/122/2024 DATED : 03/10/2024	
SANCTIONED NO. B.P./WAKAD/159/2024 DATED : 27/12/2024	

Sanctioned No. B.P./Wakad/26/2025
Subject to conditions mentioned in the Office Order No.
aven dated 26/03/2025
Pimpri
Date :26/3/2025

O. C. Signed by City Engineer

for City Engineer
Building Permission Dept.
PCMC, Pimpri, Pune-18.

Pimpri Chinchwad Municipal Corporation ESTD. 11/10/82

FORM OF STATEMENT 2 PROPOSED BUILDING-(WING A1-A2, WING B1-B2, C1-C2, D1-D2, E1-E2 (RESI.+INCLUSIVE HOUSING), F1-F2, G1-G2, CLUB HOUSE-1 & CLUB HOUSE-2)

SR. NO.	BUILDING	FLOORS	COMMERCIAL F.S.I.	RESIDENTIAL F.S.I.	INCLUSIVE HOUSING F.S.I.	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	TENEMENTS SALE	TENEMENTS INCLUSIVE HOUSING
1	WING A1-A2 (COMM.+RESI.)	B1+GR.+34 FLRS. HT.=109.225 M.	1362.69	29646.57	---	31009.26	24.60	5.29	350.76	256	---
2	WING B1-B2 (COMM.+RESI.)	B1+GR.+34+35/AMENITY FLRS. HT.=113.60M.	1737.16	26752.16	---	28489.32	18.21	6.37	270.24	220	---
3	WING C1-C2 (RESI.)	B1+GR.+34+35/AMENITY FLRS. HT.=109.30 M.	---	27260.22	---	27260.22	18.21	6.37	270.24	224	---
4	WING D1-D2 (RESI.)	B1+GR.+34 FLRS. HT.=100.255 M.	---	29156.10	---	29156.10	24.60	5.29	291.70	252	---
5	WING E1-E2 (RESI.+INCLUSIVE HOUSING)	B2+B1+GR.+34+35/AMENITY FLRS. HT.=109.70 M.	---	20147.40	3185.14	20147.40	21.53	5.29	325.56	222	37
6	WING F1-F2 (COMM.+RESI.)	B2+B1+GR.+34+35/AMENITY FLRS. HT.=109.70 M.	140.57	29872.16	---	30012.73	24.60	5.29	478.38	256	---
7	WING G1-G2 (COMM.+RESI.)	B2+B1+GR.+1ST FLRS. HT.=9.575 M.	430.67	631.93	---	1062.60	15.89	7.01	---	4	---
8	CLUB HOUSE-01	GR.+01 FLR. FROM PODIUM (4TH & 5TH FLR.) HT.=6.55 M.	914.93	---	---	914.93	---	---	---	---	---
9	CLUB HOUSE-02	GR.+01 FLR. FROM PODIUM (3RD & 4TH FLR.) HT.=6.55 M.	462.82	---	---	462.82	---	---	---	---	---
	TOTAL		5048.84	163466.54	3185.14	168515.38	147.64	40.91	1986.88	1434	37
											1471

WATER CALCULATION (WING A1-A2, B1-B2, C1-C2, D1-D2, E1-E2 (SALE+INCLUSIVE HOUSING), F1-F2, G1-G2, CLUB HOUSE-01 & CLUB HOUSE-02)

	TENEMENT	NO.OF PERSONS/ TENEMENT	WATER REQUIRED PER PERSON	O.H.W.T. CAPACITY REQUIRED (LTRS.)	O.H.W.T. CAPACITY REQUIRED (LTRS.) FIRE FIGHTING		U.G.T. CAPACITY	U.G.T. CAPACITY REQUIRED(LTRS.)			U.G.T CAPACITY REQUIRED (LTRS.) FIRE FIGHTING		
WING A1-A2 (COMM.+RESI)	256	05	135	172800.00	180990.00	+ 25000.00	205990.00	205990.00	180990.00	X 2.00	361980.00	361980.00	361980.00	+ 100000.00	461980.00
	182	45	8190.00												
WING B1-B2 (COMM.+RESI)	220	05	135	148500.00	158445.00	+ 25000.00	183445.00	183445.00	158445.00	X 2.00	316890.00	316890.00	316890.00	+ 100000.00	416890.00
	221	45	9945.00												
WING C1-C2 (RESI.)	224	05	135	151200.00	151200.00	+ 25000.00	176200.00	176200.00	151200.00	X 2.00	302400.00	302400.00	302400.00	+ 100000.00	402400.00
WING D1-D2 (RESI.)	252	05	135	170100.00	170100.00	+ 25000.00	195100.00	195100.00	170100.00	X 2.00	340200.00	340200.00	340200.00	+ 100000.00	440200.00
WING E1-E2 (RESI.+INCL.HOUSING)	259	05	135	174825.00	174825.00	+ 25000.00	199825.00	199825.00	174825.00	X 2.00	349650.00	349650.00	349650.00	+ 100000.00	449650.00
WING F1-F2 (RESI.)	256	05	135	172800.00	172800.00	+ 25000.00	197800.00	197800.00	172800.00	X 2.00	345600.00	345600.00	345600.00	+ 100000.00	445600.00
WING G1-G2 (COMM.+RESI)	4	05	135	2700.00	8415.00	+ 0.00	8415.00	8415.00	8415.00	X 2.00	16830.00	16830.00	16830.00	+ 0.00	16830.00
	127	45	5715.00												
CLUB HOUSE-01, CLUB HOUSE-02 & BUSINESS LOUNGE (COMM.)	286	45	12870.00	12870.00	+ 0.00	12870.00	12870.00	12870.00	X 2.00	25740.00	25740.00	25740.00	+ 0.00	25740.00
TOTAL (RESI.+COMM.)			1029645.00	1029645.00	+ 150000.00	1179645.00	(PROVIDED) 1179645.00	1029645.00	X 2.00	2059290.00	2059290.00	2059290.00	+ 600000.00	2659290.00	(PROVIDED) 2659290.00

OCCUPANT LOAD CALCULATION (WING B1-B2) (AMENITY)

FLOOR	CARPET AREA	OCCUPANCY LOAD PER SQ.M.	PERSONS	MALE	FEMALE
1ST FLOOR	420.85	6	70	35	35
2ND FLOOR	555.32	6	93	47	46
TOTAL	976.17		163	82	81

OCCUPANT LOAD CALCULATION (WING B1-B2) (SHOPS)

FLOOR	CARPET AREA	OCCUPANCY LOAD PER SQ.M.	PERSONS	MALE	FEMALE
GROUND FL.	141.18	3	47	24	23
1ST FLOOR	64.38	6	11	6	5
TOTAL	205.56		58	30	28

SANITATION REQUIREMENT-(COMM.) (WING B1-B2) (AMENITY)

TOTAL NO OF PERSONS = 163 PERSONS
GENTS = 82 NOS. LADIES = 81 NOS.
SANITATION REQUIREMENTS- MERCANTILE WINGS, COMMERCIAL COMPLEXES, SHOPPING MALLS, FRUIT& VEGETABLE MARKETS

FIXTURES	MALE	FEMALE	REQUIRED M	REQUIRED F	PROPOSED M	PROPOSED F
WATER-CLOSETS	1 FOR UP TO 15 2 FOR 16-35 3 FOR 36-65 4 FOR 66-100	1 FOR UP TO 12 2 FOR 13-25 3 FOR 26-40 4 FOR 41-57 5 FOR 58-77 6 FOR 78-100	3	5	3	5
URINALS	NIL UP TO 6 1 FOR 7-20 2 FOR 21-45 3 FOR 46-70 4 FOR 71-100	-	3	-	3	-

SANITATION REQUIREMENT-(COMM.) (WING B1-B2) (SHOPS)

TOTAL NO OF PERSONS = 58 PERSONS
GENTS = 30 NOS. LADIES = 28 NOS.
SANITATION REQUIREMENTS- MERCANTILE WINGS, COMMERCIAL COMPLEXES, SHOPPING MALLS, FRUIT& VEGETABLE MARKETS

FIXTURES	MALE	FEMALE	REQUIRED M	REQUIRED F	PROPOSED M	PROPOSED F
WATER-CLOSETS	1 FOR UP TO 15 2 FOR 16-35 3 FOR 36-65 4 FOR 66-100	1 FOR UP TO 12 2 FOR 13-25 3 FOR 26-40 4 FOR 41-57 5 FOR 58-77 6 FOR 78-100	2	2	2	2
URINALS	NIL UP TO 6 1 FOR 7-20 2 FOR 21-45 3 FOR 46-70 4 FOR 71-100	-	2	-	2	-

REFUGE AREA STATEMENT

WING	FLOOR	REQUIRED REFUGE AREA.	PROPOSED REFUGE AREA.
WING A1-A2	7TH FLOOR	58.18	58.46
	12TH FLOOR	58.18	58.46
	17TH FLOOR	58.18	58.46
	22ND FLOOR	58.18	58.46
	27TH FLOOR	58.18	58.46
	32ND FLOOR	58.18	58.46
WING B1-B2	7TH FLOOR	44.93	45.04
	12TH FLOOR	44.93	45.04
	17TH FLOOR	44.93	45.04
	22ND FLOOR	44.93	45.04
	27TH FLOOR	44.93	45.04
	32ND FLOOR	44.93	45.04
WING C1-C2	8TH FLOOR	44.98	45.04
	13TH FLOOR	44.98	45.04
	18TH FLOOR	44.98	45.04
	23RD FLOOR	44.98	45.04
	28TH FLOOR	44.98	45.04
	33RD FLOOR	44.98	45.04
WING D1-D2	10TH FLOOR	58.32	58.34
	15TH FLOOR	58.32	58.34
	20TH FLOOR	58.32	58.34
	25TH FLOOR	58.32	58.34
	30TH FLOOR	58.32	58.34
WING E1-E2	8TH FLOOR	43.25	54.26
	13TH FLOOR	43.25	54.26
	18TH FLOOR	43.25	54.26
	23RD FLOOR	43.25	54.26
	28TH FLOOR	43.25	54.26
	33RD FLOOR	43.25	54.26
WING F1-F2	8TH FLOOR	56.58	79.73
	13TH FLOOR	56.58	79.73
	18TH FLOOR	56.58	79.73
	23RD FLOOR	56.58	79.73
	28TH FLOOR	56.58	79.73
	33RD FLOOR	56.58	79.73

FORM OF STATEMENT 2 PROPOSED BUILDING (WING G1-G2)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (RESI.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.+RESI.)	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS
BASEMENT-02	---	---	---				---
BASEMENT-01	---	17.26	17.26				---
GROUND FL.	430.67	52.24	482.91				---
1ST FLOOR	---	562.43	562.43	15.89	7.01		4
TOTAL	430.67	631.93	1062.60	15.89	7.01	---	4

FORM OF STATEMENT 2 PROPOSED BUILDING (CLUB HOUSE-01)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.)
GROUND FLOOR (4TH FLOOR)	563.08
1ST FLOOR (5TH FLOOR)	351.85
TOTAL	914.93

FORM OF STATEMENT 2 PROPOSED BUILDING (CLUB HOUSE-02)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.)
GROUND FLOOR (3RD FLOOR)	345.72
1ST FLOOR (4TH FLOOR)	117.10
TOTAL	462.82

FORM OF STATEMENT 2 PROPOSED BUILDING (WING A1-A2)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (RESI.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.+RESI.)	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS
BASEMENT-01	---	---	---				---
GROUND FL.	467.39	4.95	472.34				---
1ST FLOOR	463.14	15.02	478.16	24.60	5.29		---
2ND FLOOR	215.45	542.51	757.96				4
3RD FLOOR	216.71	523.23	739.94				4
4TH FLOOR	---	911.96	911.96				8
5TH FLOOR	---	929.88	929.88				8
6TH FLOOR	---	929.88	929.88				8
7TH FLOOR (R)	---	888.63	888.63			58.46	8
8TH FLOOR	---	929.88	929.88				8
9TH FLOOR	---	929.88	929.88				8
10TH FLOOR	---	929.88	929.88				8
11TH FLOOR	---	929.88	929.88				8
12TH FLOOR (R)	---	888.63	888.63			58.46	8
13TH FLOOR	---	929.88	929.88				8
14TH FLOOR	---	929.88	929.88				8
15TH FLOOR	---	929.88	929.88				8
16TH FLOOR	---	929.88	929.88				8
17TH FLOOR (R)	---	888.63	888.63			58.46	8
18TH FLOOR	---	929.88	929.88				8
19TH FLOOR	---	929.88	929.88				8
20TH FLOOR	---	929.88	929.88				8
21ST FLOOR	---	929.88	929.88				8
22ND FLOOR (R)	---	888.63	888.63			58.46	8
23RD FLOOR	---	929.88	929.88				8
24TH FLOOR	---	929.88	929.88				8
25TH FLOOR	---	929.88	929.88				8
26TH FLOOR	---	929.88	929.88				8
27TH FLOOR (R)	---	888.63	888.63			58.46	8
28TH FLOOR	---	929.88	929.88				8
29TH FLOOR	---	929.88	929.88				8
30TH FLOOR	---	929.88	929.88				8
31ST FLOOR	---	929.88	929.88				8
32ND FLOOR (R)	---	888.63	888.63			58.46	8
33RD FLOOR	---	929.88	929.88				8
34TH FLOOR	---	929.88	929.88				8
TOTAL	1362.69	29646.57	31009.26	24.60	5.29	350.76	256

FORM OF STATEMENT 2 PROPOSED BUILDING (WING B1-B2)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (RESI.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.+RESI.)	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS
BASEMENT-01	---	---	---				---
GROUND FL.	159.72	30.94	190.66				---
1ST FLOOR	695.49	20.96	716.45	18.21	6.37		---
2ND FLOOR	740.80	4.23	745.03				---
3RD FLOOR	---	615.38	615.38				5
4TH FLOOR	---	728.29	728.29				6
5TH FLOOR	---	744.01	744.01				6
6TH FLOOR	---	853.43	853.43				7
7TH FLOOR (R)	---	828.92	828.92			45.04	7
8TH FLOOR	---	853.70	853.70				7
9TH FLOOR	---	853.70	853.70				7
10TH FLOOR	---	853.70	853.70				7
11TH FLOOR	---	853.70	853.70				7
12TH FLOOR (R)	---	828.92	828.92			45.04	7
13TH FLOOR	---	853.70	853.70				7
14TH FLOOR	---	853.70	853.70				7
15TH FLOOR	---	853.70	853.70				7
16TH FLOOR	---	853.70	853.70				7
17TH FLOOR (R)	---	828.92	828.92			45.04	7
18TH FLOOR	---	853.70	853.70				7
19TH FLOOR	---	853.70	853.70				7
20TH FLOOR	---	853.70	853.70				7
21ST FLOOR	---	853.70	853.70				7
22ND FLOOR (R)	---	828.92	828.92			45.04	7
23RD FLOOR	---	853.70	853.70				7
24TH FLOOR	---	853.70	853.70				7
25TH FLOOR	---	853.70	853.70				7
26TH FLOOR	---	853.70	853.70				7
27TH FLOOR (R)	---	828.92	828.92			45.04	7
28TH FLOOR	---	853.70	853.70				7
29TH FLOOR	---	853.70	853.70				7
30TH FLOOR	---	853.70	853.70				7
31ST FLOOR	---	853.70	853.70				7
32ND FLOOR (R)	---	828.92	828.92			45.04	7
33RD FLOOR	---	853.70	853.70				7
34TH FLOOR	---	853.70	853.70				7
35TH/AMENITY/ TERRACE FLOOR	141.15	---	141.15				0
TOTAL	1737.16	26752.16	28489.32	18.21	6.37	270.24	220

FORM OF STATEMENT 2 PROPOSED BUILDING (WING C1-C2)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR,AS PER OUTER CONSTRUCTION LINE.	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS
BASEMENT-01	---				---
GROUND FL.	---				---
1ST FLOOR	30.32				---
2ND FLOOR	534.48	18.21	6.37		04
3RD FLOOR	612.19				05
4TH FLOOR	729.82				06
5TH FLOOR	744.44				06
6TH FLOOR	853.65				07
7TH FLOOR	853.65				07
8TH FLOOR (R)	829.17			45.04	07
9TH FLOOR	853.65				07
10TH FLOOR	853.65				07
11TH FLOOR	853.65				07
12TH FLOOR	853.65				07
13TH FLOOR (R)	829.17			45.04	07
14TH FLOOR	853.65				07
15TH FLOOR	853.65				07
16TH FLOOR	853.65				07
17TH FLOOR	853.65				07
18TH FLOOR (R)	829.17			45.04	07
19TH FLOOR	853.65				07
20TH FLOOR	853.65				07
21TH FLOOR	853.65				07
22TH FLOOR	853.65				07
23RD FLOOR (R)	829.17			45.04	07
24TH FLOOR	853.65				07
25TH FLOOR	853.65				07
26TH FLOOR	853.65				07
27TH FLOOR	853.65				07
28TH FLOOR (R)	829.17			45.04	07
29TH FLOOR	853.65				07
30TH FLOOR	853.65				07
31ST FLOOR	853.65				07
32ND FLOOR	853.65				07
33RD FLOOR (R)	829.17			45.04	07
34TH FLOOR	853.65				07
35/AMENITY/ TERRACE FLOOR	---				---
TOTAL	27260.22	18.21	6.37	270.24	224

FORM OF STATEMENT 2 PROPOSED BUILDING (WING D1-D2)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE.	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS
BASEMENT-01	---				---
GROUND FL.	4.99				---
1ST FLOOR	32.21				---
2ND FLOOR	17.07				---
3RD FLOOR	519.97	24.60	5.29		04
4TH FLOOR	910.81				08
5TH FLOOR	929.20				08
6TH FLOOR	929.20				08
7TH FLOOR	929.20				08
8TH FLOOR	929.20				08
9TH FLOOR	929.20				08
10TH FLOOR (R)	888.21			58.34	08
11TH FLOOR	929.20				08
12TH FLOOR	929.20				08
13TH FLOOR	929.20				08
14TH FLOOR	929.20				08
15TH FLOOR (R)	888.21			58.34	08
16TH FLOOR	929.20				08
17TH FLOOR	929.20				08
18TH FLOOR	929.20				08
19TH FLOOR	929.20				08
20TH FLOOR (R)	888.21			58.34	08
21TH FLOOR	929.20				08
22TH FLOOR	929.20				08
23TH FLOOR	929.20				08
24TH FLOOR	929.20				08
25TH FLOOR (R)	888.21			58.34	08
26TH FLOOR	929.20				08
27TH FLOOR	929.20				08
28TH FLOOR	929.20				08
29TH FLOOR	929.20				08
30TH FLOOR (R)	888.21			58.34	08
31TH FLOOR	929.20				08
32TH FLOOR	929.20				08
33TH FLOOR	929.20				08
34TH FLOOR	929.20				08
TOTAL	29156.10	24.60	5.29	291.70	252

FORM OF STATEMENT 2 PROPOSED BUILDING (WING E1-E2) (RESI.+INCLUSIVE HOUSING)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (RESI.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE (INCLUSIVE HOUSING)	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS SALE	NOS. OF TENEMENTS INCLUSIVE HOUSING
BASEMENT-02	---	---				---	---
BASEMENT-01	---	---				---	---
GROUND FL.	41.40	---				---	---
1ST FLOOR	4.21	400.52				---	---
2ND FLOOR	1.07	540.91	21.53	5.29		---	---
3RD FLOOR	---	609.37				---	06
4TH FLOOR	---	677.14				---	06
5TH FLOOR	---	677.14				---	06
6TH FLOOR	415.64	280.06				04	04
7TH FLOOR	714.02	---				08	---
8TH FLOOR (R)	662.44	---			54.26	07	---
9TH FLOOR	714.02	---				08	---
10TH FLOOR	714.02	---				08	---
11TH FLOOR	714.02	---				08	---
12TH FLOOR	714.02	---				08	---
13TH FLOOR (R)	662.44	---			54.26	07	---
14TH FLOOR	714.02	---				08	---
15TH FLOOR	714.02	---				08	---
16TH FLOOR	714.02	---				08	---
17TH FLOOR	714.02	---				08	---
18TH FLOOR (R)	662.44	---			54.26	07	---
19TH FLOOR	714.02	---				08	---
20TH FLOOR	714.02	---				08	---
21TH FLOOR	714.02	---				08	---
22TH FLOOR	714.02	---				08	---
23RD FLOOR (R)	662.44	---			54.26	07	---
24TH FLOOR	714.02	---				08	---
25TH FLOOR	714.02	---				08	---
26TH FLOOR	714.02	---				08	---
27TH FLOOR	714.02	---				08	---
28TH FLOOR (R)	662.44	---			54.26	07	---
29TH FLOOR	714.02	---				08	---
30TH FLOOR	714.02	---				08	---
31ST FLOOR	714.02	---				08	---
32ND FLOOR	714.02	---				08	---
33RD FLOOR (R)	662.44	---			54.26	07	---
34TH FLOOR	714.02	---				08	---
35TH/AMENITY/ TERRACE FLOOR	---	---				---	---
TOTAL	20147.40	3185.14	21.53	5.29	325.56	222	37
							259

FORM OF STATEMENT 2 PROPOSED BUILDING (WING F1-F2)

FLOOR'S NAME	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (RESI.)	TOTAL BUILT-UP AREA OF FLOOR, AS PER OUTER CONSTRUCTION LINE. (COMM.+RESI.)	LIFT AREA	FIRE LIFT AREA	REFUGE AREA	NOS. OF TENEMENTS
BASEMENT-02	---	---	---				---
BASEMENT-01	---	---	---				---
GROUND FL.	---	41.01	41.01				---
1ST FLOOR	---	530.06	530.06				04
2ND FLOOR	---	525.55	525.55	24.60	5.29		04
3RD FLOOR	---	773.48	773.48				07
4TH FLOOR	---	791.40	791.40				07
5TH FLOOR	---	922.97	922.97				08
6TH FLOOR	---	922.97	922.97				08
7TH FLOOR	---	922.97	922.97				08
8TH FLOOR (R)	---	843.23	843.23			79.73	07
9TH FLOOR	---	922.97	922.97				08
10TH FLOOR	---	922.97	922.97				08
11TH FLOOR	---	922.97	922.97				08
12TH FLOOR	---	922.97	922.97				08
13TH FLOOR (R)	---	843.23	843.23			79.73	07
14TH FLOOR	---	922.97	922.97				08
15TH FLOOR	---	922.97	922.97				08
16TH FLOOR	---	922.97	922.97				08
17TH FLOOR	---	922.97	922.97				08
18TH FLOOR (R)	---	843.23	843.23			79.73	07
19TH FLOOR	---	922.97	922.97				08
20TH FLOOR	---	922.97	922.97				08
21TH FLOOR	---	922.97	922.97				08
22TH FLOOR	---	922.97	922.97				08
23RD FLOOR (R)	---	843.23	843.23			79.73	07
24TH FLOOR	---	922.97	922.97				08
25TH FLOOR	---	922.97	922.97				08
26TH FLOOR	---	922.97	922.97				08
27TH FLOOR	---	922.97	922.97				08
28TH FLOOR (R)	---	843.23	843.23			79.73	07
29TH FLOOR	---	922.97	922.97				08
30TH FLOOR	---	922.97	922.97				08
31ST FLOOR	---	922.97	922.97				08
32ND FLOOR	---	922.97	922.97				08
33RD FLOOR (R)	---	843.23	843.23			79.73	07
34TH FLOOR	---	922.97	922.97				08
35TH/AMENITY/ TERRACE FLOOR	140.57	---	140.57				---
TOTAL	140.57	29872.16	30012.73	24.60	5.29	478.38	256

OCCUPANT LOAD CALCULATION (WING A1-A2)

FLOOR	CARPET AREA	OCCUPANCY LOAD PER SQ.M.	PERSONS	MALE	FEMALE
GROUND FLOOR	382.05	3	127	64	63
1ST FLOOR	327.16	6	55	28	27
TOTAL	709.21		182	92	90

SANITATION REQUIREMENT-(COMM.) (WING A1-A2)

TOTAL NO OF PERSONS = 182 PERSONS
GENTS = 92 NOS. LADIES = 90 NOS.
SANITATION REQUIREMENTS- MERCANTILE WINGS, COMMERCIAL COMPLEXES, SHOPPING MALLS, FRUIT& VEGETABLE MARKETS

FIXTURES	MALE	FEMALE	REQUIRED M	REQUIRED F	PROPOSED M	PROPOSED F
WATER-CLOSETS	1 FOR UP TO 15 2 FOR 16-35 3 FOR 36-65 4 FOR 66-100	1 FOR UP TO 12 2 FOR 13-25 3 FOR 26-40 4 FOR 41-57 5 FOR 58-77 6 FOR 78-100	4	5	4	5
URINALS	NIL UP TO 6 1 FOR 7-20 2 FOR 21-45 3 FOR 46-70 4 FOR 71-100	-	4	-	4	-

OCCUPANT LOAD CALCULATION (WING G1-G2)

FLOOR	CARPET AREA	OCCUPANCY LOAD PER SQ.M.	PERSONS	MALE	FEMALE
GROUND FLOOR	381.32	3	127	64	63
TOTAL	381.32		127	64	63

SANITATION REQUIREMENT-(COMM.